

**ADDENDUM N0.1
TO THE INVITATION TO BID**

**KCKHA Project #19-07-57 (22)
HVAC Replacement Westgate Villa**

ISSUED: June 6, 2019

The additions and revisions to the invitation to bid, plans and specifications as listed herein shall be included in the bid for this work and shall form part of the Work under the Contract.

GENERAL:

The pre-bid meeting was held on Wednesday, May 22, 2019 at 10:00 a.m. at the Main Office, Board Room, 1124 North 9th Street, Kansas City, Kansas. A copy of the minutes is attached and is part of the addendum.

SPECIFICATION SECTION 01010-SUMMARY OF THE WORK

DIVISION 15/DIVISION 16 PROVISIONS:

Description of Work: Installation

5. Replace the existing sentence with new sentence as follows: “Reuse existing condensing unit branch circuits, and install new motor disconnect switches, flexible runouts and overcurrent protective devices. Refer to Specification Section 16120 for Field Quality Control requirements.”

DRAWING PME1

1. In “Equipment Data Schedule”

For CC-2: Change “1BR Units” to “2BR Units”.

2. In “Section 15050: Part 3-Execution, Selective Demolition”

For Paragraph “Materials and Equipment to be Salvaged”, add the following sentence. “Five (5) condensing units shall remain the property of the KCKHA.”

DRAWING PME2

1. In “Keyed Notes”

Delete Keynote 4. All motor disconnect switches shall be replaced.

- 2. Replace Keynote 8 with new Keynote 8 as follows: “Reuse existing condensing unit branch circuits, and install new motor disconnect switches, flexible runouts and overcurrent protective devices. Refer to Specification Section 16120 for Field Quality Control requirements.”**